

# *BRUHAT BANGALORE MAHANAGARA PALIKE*

## *YELAHANKA ZONE*

### *DIVISION: BYATARAYANAPURA*

### *SUB DIVISION: VIDYARANYAPURA*

***Name of Work:*** ***Estimate for Filling of Pot holes at Ganeshanagara, Telecom Layout, Thindlu, Doddabommasandra and Surrounding areas in Ward No. 09, (Vidyaranyapura). For the year 2019-20.***

***Job Code:*** 009-20-000089

***Estimated Cost Rs. 15.00 Lakhs***

# BRUHAT BANGALORE MAHANAGARA PALIKE

## YELAHANKA ZONE

**Name of Work: Estimate for Filling of Pot holes at Ganeshanagara, Telecom Layout, Thindlu, Doddabommasandra and Surrounding areas in Ward No. 09, (Vidyaranyapura). For the year 2019-20.**

| | | Estimate Cost Rs. | | | | | | 1500000.00 | |
|---|---|---|---|---|---|---|---|---|---|
| Sl No | Description of item | Unit | No | L | B | D | Qty | Rate | Amount |
| 1 | KSRRB M400- Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 **Page No. 155 / Item No. 20.18, PWD SR 2018-19** | Cum | | | | | | | |
| | Road Cut Portion and Depression Filling | | | | | | | | |
| | Ganeshanagara Main Road | | 2 | 1.20 | 1.30 | 0.15 | 0.47 | | |
| | | | 2 | 2.00 | 1.50 | 0.15 | 0.90 | | |
| | | | 2 | 2.50 | 2.20 | 0.15 | 1.65 | | |
| | | | 3 | 2.00 | 1.30 | 0.15 | 1.17 | | |
| | 1st Cross | | 5 | 2.80 | 2.00 | 0.15 | 4.20 | | |
| | | | 2 | 3.50 | 2.50 | 0.15 | 2.63 | | |
| | | | 2 | 1.80 | 5.00 | 0.15 | 2.70 | | |
| | | | 3 | 3.60 | 2.00 | 0.15 | 3.24 | | |
| | 2nd Cross | | 2 | 2.80 | 3.20 | 0.15 | 2.69 | | |
| | | | 5 | 3.10 | 1.50 | 0.15 | 3.49 | | |
| | | | 2 | 3.80 | 4.00 | 0.15 | 4.56 | | |
| | | | 3 | 2.90 | 1.10 | 0.15 | 1.44 | | |
| | 3rd Cross | | 2 | 3.00 | 1.60 | 0.15 | 1.44 | | |
| | | | 2 | 2.50 | 1.60 | 0.15 | 1.20 | | |
| | | | 2 | 2.50 | 1.50 | 0.15 | 1.13 | | |
| | 4th Cross | | 3 | 1.50 | 1.80 | 0.15 | 1.22 | | |
| | | | 2 | 2.00 | 2.00 | 0.15 | 1.20 | | |
| | | | 2 | 2.50 | 2.50 | 0.15 | 1.88 | | |
| | | | 3 | 4.50 | 3.50 | 0.15 | 7.09 | | |
| | | | 2 | 2.00 | 2.00 | 0.15 | 1.20 | | |
| | | | 6 | 6.00 | 3.20 | 0.15 | 17.28 | | |
| | Telecom Layout Main Road | | 2 | 6.00 | 4.00 | 0.15 | 7.20 | | |
| | | | 1 | 3.50 | 1.80 | 0.15 | 0.95 | | |
| | | | 2 | 4.50 | 3.50 | 0.15 | 4.73 | | |
| | | | 2 | 2.50 | 3.20 | 0.15 | 2.40 | | |
| | | | 2 | 3.20 | 1.60 | 0.15 | 1.54 | | |
| | | | 2 | 1.50 | 2.50 | 0.15 | 1.13 | | |
| | | | 2 | 2.90 | 3.50 | 0.15 | 3.05 | | |
| | | | 2 | 2.00 | 2.80 | 0.15 | 1.68 | | |
| | Cross Roads | | 2 | 3.00 | 1.50 | 0.15 | 1.35 | | |
| | | | 2 | 1.80 | 2.50 | 0.15 | 1.35 | | |
| | | | 5 | 5.50 | 4.10 | 0.15 | 16.91 | | |
| | | | 3 | 2.20 | 3.20 | 0.15 | 3.17 | | |
| | | | 2 | 1.90 | 1.80 | 0.15 | 1.03 | | |
| | | | 1 | 2.80 | 3.50 | 0.15 | 1.47 | | |
| | | | 2 | 2.20 | 1.50 | 0.15 | 0.99 | | |
| | | | 3 | 3.50 | 3.50 | 0.15 | 5.51 | | |
| | | | 4 | 3.50 | 3.00 | 0.15 | 6.30 | | |
| | | | 2 | 2.00 | 3.20 | 0.15 | 1.92 | | |
| | | | 2 | 3.00 | 1.80 | 0.15 | 1.62 | | |
| | | | 1 | 2.80 | 1.00 | 0.15 | 0.42 | | |
| | | | 7 | 3.00 | 3.00 | 0.15 | 9.45 | | |
| | Thindlu Surrounding areas | | 5 | 4.50 | 5.00 | 0.15 | 16.88 | | |
| | | | 2 | 2.20 | 1.10 | 0.15 | 0.73 | | |

| Sl No | Description of item | Unit | No | L | B | D | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|
| | | | 5 | 2.50 | 2.50 | 0.15 | 4.69 | | |
| | | | 2 | 1.80 | 1.00 | 0.15 | 0.54 | | |
| | | | 6 | 2.50 | 1.00 | 0.15 | 2.25 | | |
| | | | 4 | 2.00 | 1.00 | 0.15 | 1.20 | | |
| | | | 2 | 5.50 | 1.10 | 0.15 | 1.82 | | |
| | | | 2 | 2.50 | 1.00 | 0.15 | 0.75 | | |
| | | | 3 | 4.50 | 1.00 | 0.15 | 2.03 | | |
| | | | 4 | 1.80 | 1.00 | 0.15 | 1.08 | | |
| | | | 5 | 2.50 | 1.00 | 0.15 | 1.88 | | |
| | Kodigehalli | | 6 | 2.30 | 1.00 | 0.15 | 2.07 | | |
| | | | 4 | 2.50 | 1.50 | 0.15 | 2.25 | | |
| | | | 2 | 2.20 | 2.20 | 0.15 | 1.45 | | |
| | | | 6 | 4.50 | 4.00 | 0.15 | 16.20 | | |
| | | | 2 | 2.50 | 1.00 | 0.15 | 0.75 | | |
| | | | 2 | 3.50 | 1.00 | 0.15 | 1.05 | | |
| | | | 3 | 1.80 | 1.20 | 0.15 | 0.97 | | |
| | | | 1 | 2.50 | 1.00 | 0.15 | 0.38 | | |
| | | | 2 | 3.60 | 1.00 | 0.15 | 1.08 | | |
| | Bullet Krishnappa Layout | | 1 | 1.50 | 1.00 | 0.15 | 0.23 | | |
| | | | 3 | 1.60 | 1.00 | 0.15 | 0.72 | | |
| | | | 2 | 1.50 | 1.00 | 0.15 | 0.45 | | |
| | | | 2 | 1.90 | 1.50 | 0.15 | 0.86 | | |
| | | | 3 | 2.50 | 1.00 | 0.15 | 1.13 | | |
| | | | 1 | 1.90 | 1.00 | 0.15 | 0.29 | | |
| | | | 2 | 8.20 | 1.00 | 0.15 | 2.46 | | |
| | | | 2 | 2.50 | 1.50 | 0.15 | 1.13 | | |
| | | | 1 | 3.20 | 1.00 | 0.15 | 0.48 | | |
| | Parwathamma Layout | | 2 | 1.80 | 1.00 | 0.15 | 0.54 | | |
| | | | 2 | 3.20 | 1.00 | 0.15 | 0.96 | | |
| | | | 2 | 3.50 | 1.00 | 0.15 | 1.05 | | |
| | | | 1 | 1.90 | 2.50 | 0.15 | 0.71 | | |
| | | | 2 | 2.30 | 1.00 | 0.15 | 0.69 | | |
| | | | 2 | 2.50 | 1.00 | 0.15 | 0.75 | | |
| | Dhanalakshmi Layout | | 1 | 4.50 | 1.10 | 0.15 | 0.74 | | |
| | | | 3 | 4.80 | 1.50 | 0.15 | 3.24 | | |
| | | | 3 | 4.90 | 1.10 | 0.15 | 2.43 | | |
| | | | 2 | 4.00 | 1.10 | 0.15 | 1.32 | | |
| | | | 1 | 5.00 | 1.00 | 0.15 | 0.75 | | |
| | | | 2 | 4.80 | 1.00 | 0.15 | 1.44 | | |
| | | | 3 | 4.50 | 1.00 | 0.15 | 2.03 | | |
| | | | 2 | 3.50 | 1.00 | 0.15 | 1.05 | | |
| | Canara Bank Layout | | 2 | 2.50 | 1.00 | 0.15 | 0.75 | | |
| | | | 2 | 5.50 | 1.00 | 0.15 | 1.65 | | |
| | | | 2 | 2.50 | 1.00 | 0.15 | 0.75 | | |
| | | | 4 | 5.50 | 0.50 | 0.15 | 1.65 | | |
| | | | 2 | 5.00 | 0.50 | 0.15 | 0.75 | | |
| | | | 4 | 5.00 | 0.50 | 0.15 | 1.50 | | |
| | | | 3 | 5.50 | 3.20 | 0.15 | 7.92 | | |
| | | | 2 | 6.40 | 3.70 | 0.15 | 7.10 | | |
| | | | 2 | 2.10 | 1.80 | 0.15 | 1.13 | | |
| | | | 1 | 4.60 | 3.60 | 0.15 | 2.48 | | |
| | | | 2 | 4.40 | 2.30 | 0.15 | 3.04 | | |
| | | | 3 | 6.50 | 1.40 | 0.15 | 4.10 | | |
| | | | 3 | 6.90 | 1.20 | 0.15 | 3.73 | | |
| | Ananda Layout | | 2 | 9.20 | 1.60 | 0.15 | 4.42 | | |
| | | | 2 | 2.40 | 1.30 | 0.15 | 0.94 | | |
| | | | 2 | 3.30 | 1.90 | 0.15 | 1.88 | | |
| | | | 2 | 3.40 | 2.10 | 0.15 | 2.14 | | |
| | | | 2 | 2.40 | 1.90 | 0.15 | 1.37 | | |
| | | | 3 | 3.50 | 1.00 | 0.15 | 1.58 | | |
| | | | 4 | 1.80 | 1.50 | 0.15 | 1.62 | | |
| | | | 2 | 5.40 | 1.70 | 0.15 | 2.75 | | |
| | | | 2 | 5.70 | 3.70 | 0.15 | 6.33 | | |
| | | | 2 | 3.00 | 0.90 | 0.15 | 0.81 | | |
| | | | 1 | 2.90 | 1.60 | 0.15 | 0.70 | | |

| Sl No | Description of item | Unit | No | L | B | D | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|
| | | | 2 | 4.60 | 1.20 | 0.15 | 1.66 | | |
| | | | 3 | 2.20 | 1.20 | 0.15 | 1.19 | | |
| | | | 2 | 3.20 | 1.70 | 0.15 | 1.63 | | |
| | | | 2 | 1.50 | 0.60 | 0.15 | 0.27 | | |
| | | | 2 | 4.50 | 2.00 | 0.15 | 2.70 | | |
| | | | 2 | 6.30 | 2.70 | 0.15 | 5.10 | | |
| | Indian Express Layout | | 2 | 1.50 | 1.30 | 0.15 | 0.59 | | |
| | | | 2 | 1.80 | 0.90 | 0.15 | 0.49 | | |
| | | | 3 | 3.20 | 1.00 | 0.15 | 1.44 | | |
| | | | 4 | 2.80 | 2.30 | 0.15 | 3.86 | | |
| | | | 4 | 6.30 | 1.20 | 0.15 | 4.54 | | |
| | | | 2 | 4.70 | 1.40 | 0.15 | 1.97 | | |
| | | | 3 | 5.30 | 0.90 | 0.15 | 2.15 | | |
| | | | 4 | 2.50 | 0.90 | 0.15 | 1.35 | | |
| | | | 2 | 1.80 | 1.90 | 0.15 | 1.03 | | |
| | | | 3 | 2.40 | 3.00 | 0.15 | 3.24 | | |
| | | | 2 | 1.80 | 2.70 | 0.15 | 1.46 | | |
| | | | | | | | **318.06** | 2001.28 | **636533.00** |
| | Basic Rate | 1888.00 | | | | | | | |
| | Area Weightage @ 6% | 113.28 | | | | | | | |
| | Total | **2001.28** | | | | | | | |
| | | | | | | | | | |
| 2 | KSRRB 3000 Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications MORTH Specification No. 3004.2 **Page No. 259 / Item No. 35.5, PWD SR 2018-19** | Sqm | | | | | | | |
| | Ganeshanagara Main Road | | 2 | 1.20 | 1.30 | | 3.12 | | |
| | | | 2 | 2.00 | 1.50 | | 6.00 | | |
| | | | 2 | 2.50 | 2.20 | | 11.00 | | |
| | | | 3 | 2.00 | 1.30 | | 7.80 | | |
| | 1st Cross | | 5 | 2.80 | 2.00 | | 28.00 | | |
| | | | 2 | 3.50 | 2.50 | | 17.50 | | |
| | | | 2 | 1.80 | 5.00 | | 18.00 | | |
| | | | 3 | 3.60 | 2.00 | | 21.60 | | |
| | 2nd Cross | | 2 | 2.80 | 3.20 | | 17.92 | | |
| | | | 5 | 3.10 | 1.50 | | 23.25 | | |
| | | | 2 | 3.80 | 4.00 | | 30.40 | | |
| | | | 3 | 2.90 | 1.10 | | 9.57 | | |
| | 3rd Cross | | 2 | 3.00 | 1.60 | | 9.60 | | |
| | | | 2 | 2.50 | 1.60 | | 8.00 | | |
| | | | 2 | 2.50 | 1.50 | | 7.50 | | |
| | 4th Cross | | 3 | 1.50 | 1.80 | | 8.10 | | |
| | | | 2 | 2.00 | 2.00 | | 8.00 | | |
| | | | 2 | 2.50 | 2.50 | | 12.50 | | |
| | | | 3 | 4.50 | 3.50 | | 47.25 | | |
| | | | 2 | 2.00 | 2.00 | | 8.00 | | |
| | | | 6 | 6.00 | 3.20 | | 115.20 | | |
| | Telecom Layout Main Road | | 2 | 6.00 | 4.00 | | 48.00 | | |
| | | | 1 | 3.50 | 1.80 | | 6.30 | | |
| | | | 2 | 4.50 | 3.50 | | 31.50 | | |
| | | | 2 | 2.50 | 3.20 | | 16.00 | | |
| | | | 2 | 3.20 | 1.60 | | 10.24 | | |
| | | | 2 | 1.50 | 2.50 | | 7.50 | | |
| | | | 2 | 2.90 | 3.50 | | 20.30 | | |
| | | | 2 | 2.00 | 2.80 | | 11.20 | | |
| | Cross Roads | | 2 | 3.00 | 1.50 | | 9.00 | | |
| | | | 2 | 1.80 | 2.50 | | 9.00 | | |

| Sl No | Description of item | Unit | No | L | B | D | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|
| | | | 5 | 5.50 | 4.10 | | 112.75 | | |
| | | | 3 | 2.20 | 3.20 | | 21.12 | | |
| | | | 2 | 1.90 | 1.80 | | 6.84 | | |
| | | | 1 | 2.80 | 3.50 | | 9.80 | | |
| | | | 2 | 2.20 | 1.50 | | 6.60 | | |
| | | | 3 | 3.50 | 3.50 | | 36.75 | | |
| | | | 4 | 3.50 | 3.00 | | 42.00 | | |
| | | | 2 | 2.00 | 3.20 | | 12.80 | | |
| | | | 2 | 3.00 | 1.80 | | 10.80 | | |
| | | | 1 | 2.80 | 1.00 | | 2.80 | | |
| | | | 7 | 3.00 | 3.00 | | 63.00 | | |
| | Thindlu Surrounding areas | | 5 | 4.50 | 5.00 | | 112.50 | | |
| | | | 2 | 2.20 | 1.10 | | 4.84 | | |
| | | | 5 | 2.50 | 2.50 | | 31.25 | | |
| | | | 2 | 1.80 | 1.00 | | 3.60 | | |
| | | | 6 | 2.50 | 1.00 | | 15.00 | | |
| | | | 4 | 2.00 | 1.00 | | 8.00 | | |
| | | | 2 | 5.50 | 1.10 | | 12.10 | | |
| | | | 2 | 2.50 | 1.00 | | 5.00 | | |
| | | | 3 | 4.50 | 1.00 | | 13.50 | | |
| | | | 4 | 1.80 | 1.00 | | 7.20 | | |
| | | | 5 | 2.50 | 1.00 | | 12.50 | | |
| | Kodigehalli | | 6 | 2.30 | 1.00 | | 13.80 | | |
| | | | 4 | 2.50 | 1.50 | | 15.00 | | |
| | | | 2 | 2.20 | 2.20 | | 9.68 | | |
| | | | 6 | 4.50 | 4.00 | | 108.00 | | |
| | | | 2 | 2.50 | 1.00 | | 5.00 | | |
| | | | 2 | 3.50 | 1.00 | | 7.00 | | |
| | | | 3 | 1.80 | 1.20 | | 6.48 | | |
| | | | 1 | 2.50 | 1.00 | | 2.50 | | |
| | | | 2 | 3.60 | 1.00 | | 7.20 | | |
| | Bullet Krishnappa Layout | | 1 | 1.50 | 1.00 | | 1.50 | | |
| | | | 3 | 1.60 | 1.00 | | 4.80 | | |
| | | | 2 | 1.50 | 1.00 | | 3.00 | | |
| | | | 2 | 1.90 | 1.50 | | 5.70 | | |
| | | | 3 | 2.50 | 1.00 | | 7.50 | | |
| | | | 1 | 1.90 | 1.80 | | 3.42 | | |
| | | | 2 | 8.20 | 2.00 | | 32.80 | | |
| | | | 2 | 2.50 | 1.50 | | 7.50 | | |
| | | | 1 | 3.20 | 1.20 | | 3.84 | | |
| | Parwathamma Layout | | 2 | 1.80 | 1.50 | | 5.40 | | |
| | | | 2 | 3.20 | 1.80 | | 11.52 | | |
| | | | 2 | 3.50 | 1.00 | | 7.00 | | |
| | | | 1 | 1.90 | 2.50 | | 4.75 | | |
| | | | 2 | 2.30 | 1.30 | | 5.98 | | |
| | | | 2 | 2.50 | 1.00 | | 5.00 | | |
| | Dhanalakshmi Layout | | 1 | 4.50 | 1.10 | | 4.95 | | |
| | | | 3 | 4.80 | 1.50 | | 21.60 | | |
| | | | 3 | 4.90 | 1.10 | | 16.17 | | |
| | | | 2 | 4.00 | 1.10 | | 8.80 | | |
| | | | 1 | 5.00 | 1.20 | | 6.00 | | |
| | | | 2 | 4.80 | 1.00 | | 9.60 | | |
| | | | 3 | 4.50 | 0.90 | | 12.15 | | |
| | | | 2 | 3.50 | 1.00 | | 7.00 | | |
| | Canara Bank Layout | | 2 | 2.50 | 1.20 | | 6.00 | | |
| | | | 2 | 5.50 | 1.00 | | 11.00 | | |
| | | | 2 | 2.50 | 0.90 | | 4.50 | | |
| | | | 4 | 5.50 | 1.00 | | 22.00 | | |
| | | | 2 | 5.00 | 0.50 | | 5.00 | | |
| | | | 4 | 5.00 | 0.50 | | 10.00 | | |
| | | | 3 | 5.50 | 3.20 | | 52.80 | | |
| | | | 2 | 6.40 | 3.70 | | 47.36 | | |
| | | | 2 | 2.10 | 1.80 | | 7.56 | | |
| | | | 1 | 4.60 | 3.60 | | 16.56 | | |
| | | | 2 | 4.40 | 2.30 | | 20.24 | | |

| Sl No | Description of item | Unit | No | L | B | D | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|
| | | | 3 | 6.50 | 1.40 | | 27.30 | | |
| | | | 3 | 6.90 | 1.20 | | 24.84 | | |
| | Ananda Layout | | 2 | 9.20 | 1.60 | | 29.44 | | |
| | | | 2 | 2.40 | 1.30 | | 6.24 | | |
| | | | 2 | 3.30 | 1.90 | | 12.54 | | |
| | | | 2 | 3.40 | 2.10 | | 14.28 | | |
| | | | 2 | 2.40 | 1.90 | | 9.12 | | |
| | | | 3 | 3.50 | 1.20 | | 12.60 | | |
| | | | 4 | 1.80 | 1.50 | | 10.80 | | |
| | | | 2 | 5.40 | 1.70 | | 18.36 | | |
| | | | 2 | 5.70 | 3.70 | | 42.18 | | |
| | | | 2 | 3.00 | 0.90 | | 5.40 | | |
| | | | 1 | 2.90 | 1.60 | | 4.64 | | |
| | | | 2 | 4.60 | 1.20 | | 11.04 | | |
| | | | 3 | 2.20 | 1.20 | | 7.92 | | |
| | | | 2 | 3.20 | 1.70 | | 10.88 | | |
| | | | 2 | 1.50 | 0.90 | | 2.70 | | |
| | | | 2 | 4.50 | 2.00 | | 18.00 | | |
| | | | 2 | 6.30 | 2.70 | | 34.02 | | |
| | Indian Express Layout | | 2 | 1.50 | 1.30 | | 3.90 | | |
| | | | 2 | 1.80 | 0.90 | | 3.24 | | |
| | | | 3 | 3.20 | 1.00 | | 9.60 | | |
| | | | 4 | 2.80 | 2.30 | | 25.76 | | |
| | | | 4 | 6.30 | 1.20 | | 30.24 | | |
| | | | 2 | 4.70 | 1.40 | | 13.16 | | |
| | | | 3 | 5.30 | 1.00 | | 15.90 | | |
| | | | 4 | 2.50 | 1.00 | | 10.00 | | |
| | | | 2 | 1.80 | 1.90 | | 6.84 | | |
| | | | 3 | 2.40 | 3.00 | | 21.60 | | |
| | | | 2 | 1.80 | 2.70 | | 9.72 | | |
| | | | | | | | **2164.02** | 324.36 | **701922.00** |
| | Revised Basic Rate | 306.00 | | | | | | | |
| | Area Weightage @ 6% | 18.36 | | | | | | | |
| | Total | **324.36** | | | | | | | |
| | | | | | | | | | |
| | Sub Total | | | | | | | | **1338455.00** |
| | GST Charges @ 12 % | | | | | | | | **160615.00** |
| | Miscellaneous and unforeseen charges | | | | | | | | **930.00** |
| | | | | | | | | **Total** | **1500000.00** |

**Rupees Fifteen Lakh(s) Only**

**CERTIFICATE:**

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per P.W.D S.R of 2018-19.
3 This work included under 2019-20 POW.
4 The provisions were made in this estimate are necessary and adequate.
5 This works come under B.B.M.P. limits.

Assistant Engineer
Ward No. 09

Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike
Vidyaranyapura Sub Division

21/04

Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Division

Administrative Approval
Accorded For RS. 15.00 Lakhs
Head of A/C P-1771
CER NO BS/138/20 Dt: 20/03/2020
21/04
TA
CE (YNK)

TECHNICAL SANCTION
Accorded For Rs. 15.00 Lakhs only
Head of A/c P1771, POW works.
Div. Ref. No. Date 24/4/2020
AE
EE(BTP)